

SECTION 00900

Addendum No. 2 (June 9, 2014)

to
Contract Documents

Town of Surfside
Surfside Seawall Replacement
TOWN RFP No. 2014-003
CGA PROJECT No. 12-5247

To All Bidders:

Bidders for the above-referenced project shall take note of the following changes, additions, deletions, clarifications, etc. to the Plans and Specifications, which in accordance with the Contract Documents shall become a part of and have precedence over anything shown or described otherwise.

IN THE CONTRACT DOCUMENTS:

1. Attached RFI Responses is **to be added** to the Contract Documents.

All other documents, specifications, drawings, terms and conditions remain the same.

Bidders must acknowledge receipt of Addendum on Page 00300-4 in Section 00300.

END OF SECTION

Responses to RFI for Addendum No.2

TOWN OF SURFSIDE
Seawall Replacement Project
Town RFP No. 2014-003
CGA Project No. 12-5247
June 9, 2013

1.) Reference: General

Question: The large black chain link fence in the Surfside Park is most likely going to have to be removed and replaced or reinstall. Is this going to be included in the scope of the contractor or the Town of Surfside?

Response: *If the fence is required to be removed, it will need to be replaced or reinstalled to as good or better condition, at the Contractor's expense.*

2.) Reference: General

Questions: Is it acceptable for the contractor to utilize the 92nd street end for storage of aggregate and lay down?

Response: *Although the street ends are public right of way, they are utilized as residential access to their driveways. Although minimal storage may be permitted, the exact locations size and extents of the area permitted for storage will need to be requested by the Contractor, reviewed by the Owner and confirmed in writing.*

3.) Reference: Request

Question: Please provide soil borings B8 and B10.

Response: *Soil borings were not performed at these locations due to the presence of FPL utilities in the vicinity of the seawalls.*

4.) Reference: Addendum, Answer to question No. 1

Request: To clarify the 10ea test pile required on the project will be Static Load Pile Test? If static load test are to be used a working load must be given to calculate the reaction frame requirements, please provide the working loads? PDA testing is an easier and more economical alternative to the static load test. Can the static load test be replaced with a PDA test?

Response: *Contractor may replace the Static Load Pile Test with PDA testing. If the Contractor is proposing the use of PDA in lieu of Static Load Pile Test, please indicate so in your bid submittal.*

5.) Reference: Drawing C11 Detail C-C and soil boring report

Question: This section notes, pile tip is to be 3ft into rock. Is the "rock" stated on in the detail referring to "Medium Dense Light Gray Sandy Lime Stone" shown on the Universal Engineering Sciences boring logs at or around 13.5 ft? An accurate prediction of pile lengths is required to properly estimate pile driving cost.

Response: *That is correct.*

6.) **Reference:** Request-Technical Specifications

Question: Please provide concrete specification 03305

Response: *Please refer to FDOT Standard Specification 346 and appertaining subsections. As a reminder, 5,000 psi concrete is to be placed in the cap, and 6,000 psi concrete in the panels and piles.*

7.) **Reference:** Request-Bid Form Item 23 Pile Splices

Request: Please provide a quantity of pile splices to allow consistent bidding of contractors?

Response: *An estimate of the required number of pile splices is 64.*

8.) **Request:** Is there an area available for a site trailer or an office that can be rented at the Surfside town hall?

Response: *No, there are currently no Town Owned areas with space for a site trailer or office.*