



**Town of Surfside**

**ITB 2023-01**

**Abbott Avenue Stormwater Improvements Project**

**Addendum No. 2**

Date Issued: March 14, 2023

To All Proposers:

Proposers for the above-referenced ITB shall take note of the following changes, additions, deletions or clarifications to ITB No. 2023-01, which in accordance with the ITB Documents shall become a part of and have precedence over anything shown or described otherwise in the ITB.

**THE FOLLOWING CHANGES ARE MADE TO THE ITB:**

- 1. Please provide the engineers estimate, calendar days for job completion, and please advise if the Underground Utility and Excavation Florida State license will satisfy the bidders qualifications.**

Response: Updated opinion of probable cost attached. The construction will take approximately 365 calendar days. We are pending confirmation from the EOR regarding the Florida Underground Utility License.

**PROPOSER:**

**NAME:** \_\_\_\_\_

**TITLE:** \_\_\_\_\_

**DATE:** \_\_\_\_\_

PROJECT TITLE		KEITH PROJECT NO.		DATE	
Abbott Avenue Drainage Improvements		11494.01		3/9/2023	
LOCATION					
91st and 92nd Street Improvements					
ESTIMATED BY: MB		CHECKED BY: CM		APPROVED BY: SW	
NO.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1	Pump Station	2	LS	\$ 400,000.00	\$800,000.00
2	Bypass Structure	2	LS	\$ 50,000.00	\$100,000.00
3	Downstream Defender	2	EA	\$ 145,750.00	\$291,500.00
4	Control Structure	2	EA	\$ 7,923.77	\$15,847.54
5	Trash Rack Structure	2	EA	\$ 12,000.00	\$24,000.00
6	Drainage Injection Wells (2-ft Dia.)	6	EA	\$ 65,000.00	\$390,000.00
7	Drainage Manhole/Catch Basin	7	EA	\$ 4,833.77	\$33,836.39
8	16-inch PVC (C-900) Forcemain Pipe (F&I)	3,521	LF	\$ 72.96	\$256,892.16
9	24-inch PVC (C-900) Forcemain Pipe (F&I)	403	LF	\$ 108.00	\$43,524.00
10	24-inch HDPE Pipe (F&I)	250	LF	\$ 108.00	\$27,000.00
11	Pipe Bedding; Joint Restraints; Temporary Pavement Materials If Apply; Material for Restoration of Asphalt	4,700	SY	\$ 25.00	\$117,500.00
12	Asphalt, Milling and Resurfacing	950	TN	\$ 118.00	\$112,100.00
				<b>Subtotal (13)</b>	<b>\$2,212,200.09</b>
14	Mobilization				\$553,050.02
15	Maintenance of Traffic (10%)				\$221,220.01
16	Construction Surveying / Stake-out / As-Built (7%)				\$154,854.01
17	Construction Material Testing				\$110,610.00
18	Dedicated Allowance - Certified Industrial Hygienist or State of Florida Licensed Engineer in Environmental Discipline to Develop Health and Safety Plan				\$25,000.00
19	Dedicated Allowance - Permit Fees, Inspections, Impact Fees (0.05) X (Subtotal, Item 13)				\$110,610.00
20	For unforeseen improvements, for minor construction changes and quantities adjustments at other intersections along 91st & 92nd Street				\$200,000.00
21	For unforeseen conditions, for minor construction changes and for quantity adjustments, if ordered by the Engineer, the sum of 10% of the Subtotal, Item 13, (.10) X (Subtotal, Item 13)				\$221,220.01
				<b>Subtotal</b>	<b>\$1,596,564.06</b>
				<b>TOTAL PROJECT COST =</b>	<b>\$3,808,764.15</b>

**NOTES:**

- Quantities were calculated based on Construction Documents dated March 2023
- The locations and sizes of the existing utilities are based on best available information and cannot be guaranteed for their accuracy.
- This estimate does not include professional services.